

令和5年度 市道中野25号線舗装修繕工事（ゼロ債務負担行為）

数量計算書

市道中野25号線 中野市大字更科・小田中

数量総括表

[illegible]

数量計算書

測点名	測 点	距 離	舗装面積			舗装切断			区画線								
			幅	平 均	面 積	左	中心・端部	右	外側左	ドット破線	中心実線	中心破線	ドット破線	外側右	停止線	マーク15cm	備考
BP	0.00		5.50				5.5								2.9		
NO.1	20.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.2	40.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.3	60.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.4	80.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.5	100.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.6	120.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.7	140.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.8	160.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.8+19.0	179.00	19.00	5.50	5.50	104.5				19.0					19.0			
NO.9+1.1	181.10	2.10	7.50	6.50	13.7				2.1					2.1			
NO.10	200.00	18.90	7.50	7.50	141.8	6.1		6.7	13.9					15.9			
NO.10+3.4	203.40	3.40	5.50	6.50	22.1				3.4					3.4			
NO.11	220.00	16.60	5.50	5.50	91.3				16.6					16.6			
NO.12	240.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.13	260.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.14	280.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.15	300.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.16	320.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.17	340.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.18	360.00	20.00	5.50	5.50	110.0				20.0					20.0			
NO.19	380.00	20.00	5.70	5.60	112.0				20.0					20.0			
NO.19+11.0	391.00	11.00	5.70	5.70	62.7				11.0					11.0			
NO.19+16.1	396.10	5.10	11.00	8.35	42.6				7.1					6.1	5.5		
NO.20+6.3	406.30		20.20				18.2										
NO.20+14.8	414.80	8.50	5.60	12.90	109.7				10.5					10.5	7.3		
NO.21+18.0	438.00	23.20	5.60	5.60	129.9		5.6		23.2					23.2			
控除																	
NO.10付近側溝柵					-1.6												
NO.14付近MH					-0.8												
NO.20付近右カーブ					-1.5												
NO.20付近左カーブ					-1.5												
NO.20付近左Co基礎					-0.6												
NO.20付近右横断側溝					-1.0												
NO.21付近側溝柵					-1.9												
合計		427.80			2,471.3	42.1			426.8	0.0	0.0	0.0	0.0	427.8	15.7	0.0	

区画線工の種類が1つのみの場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	設計計上数量(m)		
					全ての費用	機・労のみ	材料費のみ

区画線工の種類が複数ある場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	α	設計計上数量(m)		
						全ての費用	機・労のみ	材料費のみ
1	ペイント式 加熱式 溶剤型 実線 15cm 供用区間	855	3,000	0.285	3.12	-	1,334	855
69	熔融式 ゼブラ 45cm 供用区間	16	450	0.03556	3.12	-	25	16
計				0.32056				

区画線消去(ウォータージェット式)を積算に用いる場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	設計計上数量 (m)