

令和5年度 市道中野25号線舗装修繕工事その2（ゼロ債務負担行為）

数量計算書

市道中野25号線 中野市大字中野

数量総括表

[illegible]

数量計算書

測点名	測 点	距 離	舗装(舗設)面積			舗装版破碎面積			舗装切断			区画線				
			幅	平 均	面 積	幅	平 均	面 積	左	中心・端部	右	外側左	外側右	停止線	マーク15cm	備考
BP-2.2	-2.20		0.00			0.00								2.4	14.9	踏切
BP	0.00	2.20	5.80	2.90	6.4	5.80	2.90	6.4				0.0	2.2			
NO.1	20.00	20.00	5.70	5.75	115.0	5.70	5.75	115.0				20.0	20.0			
NO.2	40.00	20.00	5.50	5.60	112.0	5.50	5.60	112.0				20.0	20.0			
NO.3	60.00	20.00	5.60	5.55	111.0	5.60	5.55	111.0				20.0	20.0			
NO.4	80.00	20.00	5.60	5.60	112.0	5.60	5.60	112.0				20.0	20.0			
NO.5	100.00	20.00	5.70	5.65	113.0	5.70	5.65	113.0				20.0	20.0			
NO.6	120.00	20.00	5.60	5.65	113.0	5.60	5.65	113.0				20.0	20.0			
NO.6+4.8	124.80	4.80	5.60	5.60	26.9	5.60	5.60	26.9				4.8	4.8			
NO.6+6.5	126.50	1.70	7.60	6.60	11.2	7.60	6.60	11.2				1.7	1.7			
NO.7	140.00	13.50	7.60	7.60	102.6	7.60	7.60	102.6				13.5	13.5			
NO.7+7.0	147.00	7.00	7.60	7.60	53.2	7.60	7.60	53.2				7.0	7.0			
NO.7+8.3	148.30	1.30	5.40	6.50	8.5	5.40	6.50	8.5				1.3	1.3			
NO.8	160.00	11.70	5.40	5.40	63.2	5.40	5.40	63.2				11.7	11.7			
NO.9	180.00	20.00	5.40	5.40	108.0	5.40	5.40	108.0				20.0	20.0			
NO.10	200.00	20.00	5.40	5.40	108.0	5.40	5.40	108.0				20.0	20.0			
NO.11	220.00	20.00	5.50	5.45	109.0	5.50	5.45	109.0				20.0	20.0			
NO.12	240.00	20.00	5.50	5.50	110.0	5.50	5.50	110.0				20.0	20.0			
NO.13	260.00	20.00	5.50	5.50	110.0	5.50	5.50	110.0				20.0	20.0			
NO.14	280.00	20.00	5.50	5.50	110.0	5.50	5.50	110.0				20.0	20.0			
NO.15	300.00	20.00	5.50	5.50	110.0	5.50	5.50	110.0				20.0	20.0			
NO.15+13.7	313.70	13.70	5.50	5.50	75.4	5.50	5.50	75.4				13.7	13.7			
EP	326.00	12.30			81.9			81.9	1.5	7.0		14.0	7.3	2.6		
小計			t=5cm	平均幅5.7	1870.3		t=10cm	1870.3								
取付舗装																
Pt 17.4~24.3右		1.10	5.5~6.9	6.20	6.8	5.5~7.8	6.50	8.8			5.5		-6.9			
Pt 29.8~33.6左		1.00	3.6~3.8	3.70	3.7	3.6~3.8	3.70	3.7	3.6			-3.8				
Pt 141.4~148.2右		1.70	5.1~6.8	6.50	11.1	5.1~6.8	6.50	13.0			5.1		-1.1		5.6	T字
Pt 240.0~245.1左		2.00	4.2~5.1	4.70	9.4	4.2~5.1	4.70	9.4	4.2			-5.1				
Pt 146.0~178.0左民地		32.00	0.5	0.50	16.0	0.8	0.80	25.6	32.0							
Pt 184.0~222.0左民地		38.00	0.5	0.50	19.0	0.8	0.80	30.4	38.0							
Pt 160.0~Co天端 右		78.00	0.0	0.00	0.0	0.4	0.40	31.2								
小計			t=5cm		66.0		t=5cm	122.1								
合計		328.20			1,936.3			1,992.4	96.9			318.8	315.2	5.0	20.5	

区画線工の種類が1つのみの場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標準 作業量 (m)	①／②	設計計上数量(m)		
					全ての費用	機・労のみ	材料費のみ

区画線工の種類が複数ある場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標準 作業量 (m)	①／②	α	設計計上数量(m)		
						全ての費用	機・労のみ	材料費のみ
1	ペイント式 加熱式 溶剤型 実線 15cm 供用区間	634	3,000	0.21133	3.64	-	1,154	634
69	熔融式 ゼブラ 45cm 供用区間	5	450	0.01111	3.64	-	9	5
73	熔融式 矢印・記号・文字(15cm換算) 供用区間	21	400	0.0525	3.64	-	38	21
計				0.27494				

区画線消去(ウォータージェット式)を積算に用いる場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標準 作業量 (m)	①／②	設計計上数量 (m)