

# 数量総括表

工 種 ・ 種 別	細 別	規 格	単位	数 量	摘 要
舗装打換え工	舗装版切断		m	33	33.1
	舗装版破碎		m	3200	3,199.7
	殻運搬		m2	160	160.0
	殻処分		t	368	368
	表層	再生密粒度AS 20F t=5cm 不陸整正（補足材あり）	m2	3200	3,199.7
	アスカーブ		m	95	95
区画線工	溶融式区画線	15cm換算	m	16	16.2
	溶融式区画線		m	3	3.0
	溶融式区画線		m	3	3.0
	ペイント式区画線		m	1340	1,336.0
交通管理工	交通誘導警備員		人・日	39	39

# 数量計算書

[illegible]

# 鋪 装 面 積 計 算 書

(P. 1)

位 置	横 断 幅 員			平 均 横 断 幅 員			距 離	表層	舗装幅 上段:東側 下段:西側	舗装版切断
	表層	(控除)	(全幅)	表層	(控除)	(全幅)				
No. 36 720.00	m 5.70	m 0.20	m 5.90	m 5.70	m	m	m 0.0	m <sup>2</sup>	3.70 2.00	m 5.7
No. 36 +9.0 729.00	5.70	0.20	5.90	5.70			9.0	51.3	3.70 2.00	
No. 36 +17.0 737.00	3.05	0.20	3.25	4.38			8.0	35.0	1.50 1.55	
No. 37 740.00	3.05	0.20	3.25	3.05			3.0	9.2	1.60 1.45	
No. 38 760.00	3.30	0.20	3.50	3.18			20.0	63.6	1.80 1.50	
No. 38 +12.0 772.00	3.05	0.20	3.25	3.18			12.0	38.2	1.50 1.55	
No. 38 +17.0 777.00	3.35	0.20	3.55	3.20			5.0	16.0	1.70 1.65	
No. 39 780.00	3.35	0.20	3.55	3.35			3.0	10.1	1.70 1.65	
No. 40 800.00	4.30	0.20	4.50	3.83			20.0	76.6	2.70 1.60	
No. 40 +6.0 806.00	6.50	0.40	6.90	5.40			6.0	32.4	2.65, 2.25 1.60	
No. 41 820.00	6.30	0.40	6.70	6.40			14.0	89.6	2.00, 2.40 1.90	
No. 41 +11.0 831.00	4.15	0.20	4.35	5.23			11.0	57.5	2.10 2.05	
No. 42 840.00	4.25	0.20	4.45	4.20			9.0	37.8	1.95 2.30	
No. 43 860.00	3.50	0.20	3.70	3.88			20.0	77.6	1.80 1.70	
No. 43 +13.0 873.00	5.20	0.20	5.40	4.35			13.0	56.6	3.20 2.00	
No. 44 880.00	5.20	0.20	5.40	5.20			7.0	36.4	3.20 2.00	
No. 45 900.00	5.30	0.20	5.50	5.25			20.0	105.0	3.00 2.30	
No. 46 920.00	4.50	0.20	4.70	4.90			20.0	98.0	2.30 2.20	
No. 46 +16.0 936.00	4.50	0.20	4.70	4.50			16.0	72.0	2.50 2.00	
No. 47 940.00	6.20	0.20	6.40	5.35			4.0	21.4	4.10 2.10	
No. 48 960.00	6.20	0.20	6.40	6.20			20.0	124.0	4.20 2.00	
No. 48 +6.0 966.00	4.05	0.20	4.25	5.13			6.0	30.8	2.25 1.80	
No. 49 980.00	3.70	0.20	3.90	3.88			14.0	54.3	1.90 1.80	
No. 50 1,000.00	3.60	0.20	3.80	3.65			20.0	73.0	1.95 1.65	
No. 51 1,020.00	5.55	0.20	5.75	4.58			20.0	91.6	3.65 1.90	
No. 52 1,040.00	6.50	0.20	6.70	6.03			20.0	120.6	4.50 2.00	
No. 53 1,060.00	6.10	0.20	6.30	6.30			20.0	126.0	4.55 1.55	
No. 54 1,080.00	5.85	0.20	6.05	5.98			20.0	119.6	3.15 2.70	

# 舗 装 面 積 計 算 書

(P. 1)

位 置	横 断 幅 員			平 均 横 断 幅 員			距 離	表層	舗装幅 上段:東側 下段:西側	舗装版切断
	表層	(控除)	(全幅)	表層	(控除)	(全幅)				
No. 55 1,100.00	5.00	0.20	5.20	5.43			20.0	108.6	3.00 2.00	
No. 56 1,120.00	5.90	0.20	6.10	5.45			20.0	109.0	3.10 2.80	
No. 57 1,140.00	6.10	0.20	6.30	6.00			20.0	120.0	3.10 3.00	
No. 58 1,160.00	4.95	0.20	5.15	5.53			20.0	110.6	1.85 3.10	
No. 59 1,180.00	4.45	0.20	4.65	4.70			20.0	94.0	2.00 2.45	
No. 59 +7.0 1,187.00	6.20	0.20	6.40	5.33			7.0	37.3	3.60 2.60	
No. 60 1,200.00	6.20	0.20	6.40	6.20			13.0	80.6	3.80 2.40	
No. 60 +7.0 1,207.00	6.20	0.20	6.40	6.20			7.0	43.4	3.80 2.40	
No. 61 1,220.00	3.95	0.20	4.15	5.08			13.0	66.0	1.95 2.00	
No. 62 1,240.00	3.75	0.20	3.95	3.85			20.0	77.0	1.95 1.80	
No. 63 1,260.00	3.55	0.20	3.75	3.65			20.0	73.0	1.75 1.80	5.0
No. 64 1,280.00	3.60	0.20	3.80	3.58			20.0	71.6	1.70 1.90	
No. 65 1,300.00	3.65	0.20	3.85	3.63			20.0	72.6	1.85 1.80	
No. 66 1,320.00	3.35	0.20	3.55	3.50			20.0	70.0	1.75 1.60	
No. 67 1,340.00	3.10	0.20	3.30	3.23			20.0	64.6	1.60 1.50	
No. 68 1,360.00	3.55	0.20	3.75	3.33			20.0	66.6	1.90 1.65	
No. 68 +8.0 1,368.00	5.10	0.20	5.30	4.33			8.0	34.6	3.40 1.70	
No. 69 1,380.00	5.30	0.20	5.50	5.20			12.0	62.4	3.45 1.85	
No. 69 +8.0 1,388.00	3.60	0.20	3.80	4.45			8.0	35.6	1.90 1.70	3.4
								東側平均 西側平均	2.67 2.00	
支線										
No. 43付近	4.10	0.20	4.30	4.10			3.0	12.3		10.0
NO. 61付近	7.30	0.20	7.50	7.30			9.0	65.7		9.0
合 計							680.0	3,199.7		33.1