

令和 7 年度市道米山線舗装修繕工事

数量計算書

市道米山線 中野市大字豊津

数量総括表

工種・種別	細別	計算式	設計値	単位
舗装工	舗装版切断工	= 19.8	20	m
	舗装版破碎（掘削）	= 1031.0	1030	m ²
	舗装版殻運搬（掘削）	1031×0.05 = 51.5	52	m ³
	処分費（掘削）	1031×0.05×2.3 = 118.6	119	t
	不陸整正	= 1031.0	1030	m ²
	表層工	= 1031.0	1030	m ²

数量計算書

測点名	測 点	距 離	舗装版破碎面積			舗装面積			舗装切断		
			幅	平 均	面 積	幅	平 均	面 積	左	中心・端部	右
No. 0-1. 0 (BP)	-1. 00		5. 19			5. 19				4. 7	
NO. 0	0. 00	1. 00	5. 19	5. 19	5. 2	5. 19	5. 19	5. 2			
NO. 1	20. 00	20. 00	4. 56	4. 88	97. 6	4. 56	4. 88	97. 6			
NO. 2	40. 00	20. 00	4. 42	4. 49	89. 8	4. 42	4. 49	89. 8			
NO. 3	60. 00	20. 00	4. 36	4. 39	87. 8	4. 36	4. 39	87. 8			
NO. 4	80. 00	20. 00	4. 55	4. 46	89. 2	4. 55	4. 46	89. 2	3. 1		3. 9
NO. 5	100. 00	20. 00	4. 22	4. 39	87. 8	4. 22	4. 39	87. 8			
NO. 6	120. 00	20. 00	4. 12	4. 17	83. 4	4. 12	4. 17	83. 4			
NO. 7	140. 00	20. 00	4. 05	4. 09	81. 8	4. 05	4. 09	81. 8			
NO. 7	140. 00	0. 00	3. 85	3. 95	0. 0	3. 85	3. 95	0. 0			
NO. 8	160. 00	20. 00	4. 17	4. 01	80. 2	4. 17	4. 01	80. 2			
NO. 9	180. 00	20. 00	4. 15	4. 16	83. 2	4. 15	4. 16	83. 2			8. 1
NO. 10	200. 00	20. 00	4. 09	4. 12	82. 4	4. 09	4. 12	82. 4			
NO. 11	220. 00	20. 00	4. 10	4. 10	82. 0	4. 10	4. 10	82. 0			
NO. 12-1. 0	239. 00	19. 00	4. 52	4. 31	81. 9	4. 52	4. 31	81. 9			
控除											
NO. 0 集水樹 (0. 9×1. 5)					-1. 4			-1. 4			
合計		240. 00			1, 031. 0		4. 30	1, 031. 0			19. 8